## **RUSSELL WELDING CORP**

1665 N. PROGRESS WAY TOOELE, UT 84074 Ph# 435-882-6359 Fax 435-882-8158

## **Proposal**

Proposal Date: 2/15/2012 Proposal #: 472B

Project:

TOOELE CITY CORPORATION 90 N. MAIN TOOELE, UTAH 84074 LANDFILL

| Description  | Est. Hours/Qty. | Rate                 | Total                |
|--|-----------------|----------------------|----------------------|
| **WATER TRUCK**  |                 |                      |                      |
| Install 3" line around tank, 4 adjustable spray air operated valves, hose real with hose and sprayer, bumper and plat form plate on rear of truck to hold pump.  |                 |                      |                      |
| Material:<br>Labor:  |                 | 4,240.00<br>4,892.00 | 4,240.00<br>4,892.00 |
| Robert, I have quoted top of the line items for this truck, there are some less expensive items that we could use to bring cost down. Please feel free to contact me with any questions. Thanks, Kevin |                 |                      |                      |
|  |                 |                      |                      |
| Russell Welding.   |                 |                      |                      |
| Bil does not welledy   |                 |                      |                      |
| pump é PTO   |                 |                      | . ·                  |
| 1 call suchase   |                 | Total '              | \$9,132.00           |
| Russell Welding.  Bid does not rucked.  Pump & PTO  LANDPILL WILL purchase  & INISTALL - @ SKOV  pump/PTO/Hydraulic line   |                 |                      | ·                    |



Semi Service Inc. 4285 West 1385 South Salt Lake City, Utah 84104 Phone: 1.801.521.0360

Fax: 1.801.532.7407

Email: semi@semiservice.com

## **ESTIMATE OF REPAIR**

Quote ID: 70664

Page 1 of 2

Customer: Tooele County Solid Waste

Contact: Warner, Robert

2830 South Bauer Road Tooele UT 84074

Phone: (435) 843-4781 Fax: (435) 833-0355 Quote Number: 70664
Quote Date: 1/20/2012
Quote valid until: 3/5/2012
Salesperson: Mike Burke

Unit #: 96 Water Truck

| Year: 1996 Make: INTERNATIONAL Model: WATER TANKS Mileage: Mileage Serial #: 1F |
|---|
|---|

| QUA | NTITY | DESCRIPTION   | PARTS      | HOURS |
|-----|-------|---|------------|-------|
| 1   | EA    | Install a 4" sump in bottom of tank   | \$88.00    | 8.00  |
| 1   | EA    | Install a Hot Shift PTO for use while truck is in motion while spraying and hydraulic pump on customer's truck  ***Transmission model number required to order PTO  | \$2,450.00 | 3.60  |
| 1   | EA    | Furnish & install a two line wet kit with 30 gallon hydraulic tank with 30 gallons of hydraulic oil, hoses, fittings, and controls.   | \$3,150.00 | 15.00 |
| 1   | EA    | Furnish & Install Berkley 3" (500 gallons per minute) product pump on truck frame rail with mounting brackets.  Berkeley: FM CPLG Model no: B3ZRM   | \$1,850.00 | 6.00  |
| 1   | EA    | Install a hydraulic motor on water pump and connect hydraulic lines to system.  | \$1,492.00 | 2.00  |
| 1   | EA    | Install air actuated internal valve with control in cab.  | \$585.00   | 1.80  |
| 1   | EA    | Connect new 4" sump to inlet side of pump using 4" aluminum piping.   | \$360.00   | 7.50  |
| 1   | EA    | Fab & install 3" piping from outlet side of pump & tee off to both sides in front of tank and behind cab, install a spray head on both sides on truck. Continue 3" piping to rear of truck to the rear spray head piping. | \$855.00   | 16.00 |
| 1   | EA    | Install 4" steel piping at the rear tee'd off to both sides of tank, install two spray heads at the outside rear corners of the tank  | \$1,070.00 | 5.20  |
| 1   | EA    | Install a 4" fill line at the rear of the tank dropping into the top of tank. Install butterfly valve and camlock fitting.  | \$295.00   | 4.30  |
| 1   | EA    | Fab & install a switch control panel inside of truck cab with all valve controls and extra room on panel for additional switches for future use.  | \$308.00   | 10.00 |
| 1   | EA    | Install a electric drive hose reel with 50' of 2" hose & spray nozzle on right side frame rail. Tee into outlet side piping on pump and plum 2" piping to hose reel with 2" ball valve shut off.                          | \$2,540.00 | 6.80  |
| 1   | EA    | Remove 2" piping on rear drain line and install a manual shut off valve.  | \$105.00   | 1.00  |
| 1   | EA    | Vee out and weld crack around center tank sight glass.  | \$0.00     | 1.50  |



Semi Service Inc. 4285 West 1385 South Salt Lake City, Utah 84104 Phone: 1.801.521.0360

Fax: 1.801.532.7407

Email: semi@semiservice.com

## **ESTIMATE OF REPAIR**

Quote ID: 70664

Page 2 of 2

QUANTITY DESCRIPTION PARTS HOURS
1 EA Prep, primer, and paint as needed \$119.00 2.00

Total Parts: \$15,267.00

Supplies: \$816.30

90.7 hrs Total Labor: \$8,163.00

Sub Total: \$24,246.30 Sales Tax: \$0.00 Total Due: \$24,246.30

Customer must fill out the information below before the order can be processed.

| Customer must fill | out the information below before the order can be processed |
|--------------------|---|
| Accepted by:       |   |
| Date:              |   |
| P.O. number:       |   |

- ♦ Labor and installation is included in all pricing.
- ♦ Quoted price does not include any applicable F.E.T., sales taxes and / or delivery charges.
- ♦ Quote price does not include any unforeseen obstructions or modifications.
- Quotation valid until above stated expiration date.
- Terms are Due upon Receipt unless prior credit arrangements are made at the time of order.
- ♦ FOB Salt Lake City, Utah 84101
- ♦ 20% down payment required with special order items.

Notes: